



City of Concord, New Hampshire

PURCHASING DIVISION

COMBINED OPERATIONS & MAINTENANCE FACILITY

311 NORTH STATE STREET

CONCORD, NH 03301

(603) 225-8530 FAX: (603) 230-3656

www.concordnh.gov

December 15, 2010

ADDENDUM NUMBER TWO

B18-11

RATTLESNAKE BROOK CULVERT AND OUTFALL REPLACEMENT PROJECT US ROUTE 3 (NORTH STATE STREET) CONCORD, NH

TO ALL FIRMS OF RECORD: This addendum forms a part of and modifies the bidding and contract documents and technical specifications for the project named above. The following changes, additions, and clarifications are made to the original Contract Documents as a result of the Mandatory Pre-Bid Meeting:

1. **Question:** Is there detail coming for the headwall that is for the 60" RCP?

Answer: The concrete headwall is specified as a standard NHDOT headwall with a submittal requirement as noted in Note #5 on the General Notes (Sheet 2 of 7). No separate detail has been prepared.

2. **Question:** Sheet 7 notes a steel black fence installed at the culvert opening. Is this going to be a chain link fence, or something different? Is this to be 5 feet long?

Answer: This section of fence is intended to be the same steel fence specified in Addendum #1 to be bolted directly to the outside of the stone retaining wall. The City expects this section of fence to be about 12 feet in length.

3. **Question:** Is the 30 cy of concrete for the concrete rings or is it for something else?

Answer: The 30 cy of concrete is for the concrete collar connections to be field constructed between the new culvert and pipe and the existing stone masonry structures.

PLEASE BE ADVISED THAT THE CONTRACTOR MUST ACKNOWLEDGE RECEIPT OF
ADDENDUM ONE AND TWO ON THE BID SHEET SIGNATURE PAGE (PAGE 30).

CITY OF CONCORD, NEW HAMPSHIRE

A handwritten signature in black ink, appearing to read "Douglas B. Ross", written over a horizontal line.

DOUGLAS B. ROSS
PURCHASING MANAGER